

ADDENDUM NO. THREE

PROJECT NAME: KRANNERT BUILDING
MANAGEMENT AND ECONOMICS LIBRARY
REMODEL PHASE III - 2011

WEST LAFAYETTE, INDIANA

PURDUE PROJECT NUMBER: 11511

RQAW PROJECT NUMBER: 211-016.1

DATE OF ADDENDUM: April 1, 2011



Joe Mrak, AIA,
Indiana Registration No. AR4446

THIS ADDENDUM FORMS A PART OF THE CONTRACT DOCUMENTS AND IS ISSUED IN ACCORDANCE WITH THE INSTRUCTIONS TO BIDDERS. ACKNOWLEDGE RECEIPT OF THIS ADDENDUM BY SIGNING THE ADDENDUM ACKNOWLEDGMENT SECTION OF YOUR PROPOSAL.

SPECIFICATIONS:

1. **Specification Section No.:** 09 65 00 Resilient Flooring
Specification Line No.: Part 1.6 Qualifications, B Installer
Revise this item 'B' to read:
 - B. Installer: to be one of the 3 pre-approved installers listed in Part 1.6.C, or Meet all of the following requirements:
 1. Company specializing in performing Work of this section with minimum ten (10) years documented experience.
 2. A Company who has documented similar flooring installation experience for Purdue University (any campus)
 3. A Company who has a documented installation of a Tajima product on another project

4. The Company must have a product Rep from Tajima on hand in the field during the installation

2. **Specification Section No.:** 'K', Principal Subcontractor Questionnaire
Specification Line No.: K-2, Floor Finishes, Vinyl Plank Flooring
Use the attached Section 'K' for this section in lieu of the one previously issued, which is To be submitted by each Bidder with his Bid. Note the change as described below:
'Provide the names and contact phone numbers of three (3) Owner References Where you installed similar floor finish products'.

3. **Specification Section No.:** 09 30 00 Tile
Specification Line No.: Part 1.9 Extra Materials
Add to this item 'A':
'Supply 15% overage for GT-2 Tile. All other materials shall remain 10% overage'

DRAWINGS:

1. **Drawing Sheet No.:** P102
Drawing Sheet Title: Plumbing - First, Second and Third Floor Plans
Detail No.: -
Add: Add to sink (SK-1) a Food Waste Disposer (WD-1): In-Sink-Erator Badger 5 continuous feed, 120 Volt, 60 Hz, 1/2 HP motor with overload protector and manual reset. One year warranty on parts and labor.

Add: Add to the previous Addendum #2 electric water cooler (EWC-1) "Glass filler model 5551, push lever operated, self-closing, polished chrome - plated brass, deck mounted gooseneck cold water glass filler faucet.

2. **Drawing Sheet No.:** E103
Drawing Sheet Title: Electrical Second Floor Power Plan
Detail No.: -
Add: Move existing GFI receptacle mounted 48" in Café' 204 (L-2-2/64) to under the sink and a switch over the sink counter for new Garbage Disposal. Connect to circuit (L-2-2/64)

3. **Drawing Sheet No.:** T600
Drawing Sheet Title: Telecommunications Riser Diagram
Detail No.: -
Add: Add Riser Coax from BDF B70 to IDF 201.
Add: Add Riser Coax from BDF B70 to IDF 332.

4. **Drawing Sheet No.:** I101
 Drawing Sheet Title: First Floor Finish Plan, Finish Legend & Notes
 Item: Finish Legend, WC-1: Remarks
 Add: Micro-vent Substrate Prior to Image Printing.

5. **Drawing Sheet No.:** I101
 Drawing Sheet Title: First Floor Finish Plan, Finish Legend & Notes
 Item: Finish Legend, CL-1 (Ceiling Wood Planks)
 Add:
 'Rulon Panelized Linear Wood Ceiling System is an acceptable alternative to
 Armstrong, assuming all other characteristics of the Armstrong system as listed
 in the specs and on this Finish Legend and in the drawings is met.'

END OF ADDENDUM NO. THREE

PRINCIPAL SUBCONTRACTOR QUESTIONNAIRE

KRANNERT BUILDING MANAGEMENT AND ECONOMICS LIBRARY REMODEL PHASE III - 2011

Purdue University, West Lafayette, Indiana

Principal Subcontractor Questionnaire

Submitted by _____

(To be submitted by each Bidder with his Bid)

If awarded the complete construction contract, I/WE propose to have the following Subcontractors.

	<u>SUBCONTRACTOR - COMPLETE ADDRESS</u> (list the Subcontractor firms only)	Indicate if MBE/DBE/WBE
Selective Demolition	_____ NAME	_____
	_____ ADDRESS	
Concrete Work	_____ NAME	_____
	_____ ADDRESS	
Masonry	_____ NAME	_____
	_____ ADDRESS	
Structural Steel	_____ NAME	_____
	_____ ADDRESS	
Architectural Woodwork	_____ NAME	_____

ADDRESS

Interior Doors, Frames, and Hardware _____
NAME

ADDRESS

Rolling Security Grilles _____
NAME

ADDRESS

Aluminum Storefronts _____
NAME

ADDRESS

Sliding Mall Fronts _____
NAME

ADDRESS

Gypsum Board Assemblies _____
NAME

ADDRESS

Floor Finishes, Vinyl Plank Flooring _____
NAME

ADDRESS

REFERENCES FOR THIS INSTALLER FROM OWNERS FROM
SIMILAR FLOOR FINISH INSTALLATIONS (PROVIDE 3):

NAME PHONE

ADDRESS

NAME PHONE

ADDRESS

NAME PHONE

ADDRESS

Access Floor

NAME

ADDRESS

Paints and Coatings

NAME

ADDRESS

Mechanical Construction

NAME

ADDRESS

Fire Protection

NAME

ADDRESS

Electrical Construction

NAME

ADDRESS

Telecommunications Construction

NAME

ADDRESS

These Subcontractors have been advised of the applicable labor provisions as set forth in the Contract Documents and these labor provisions will be included in all Subcontracts.

(DATED)

(SIGNED)